BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of Work: Replace of Old UGD pipeline at Kodigehalli in ward No.08

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	43.88	KSRRB M200-12.2. Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. i) Lime /Cement Concrete. I. By Manual Means :B. Cement Concrete Grade M-15 & M-20. MORTH Specification No. 202. (P.No. 139, I.No. 18.18 of CSR 2018-19)	Cum	699.42	Rupees Six Hundred Ninety Nine and Forty Two Paise Only
2	195.48	EXCAVATING FOR PIPE LINE TRENCHES OF REQUIRED WIDTH by mechanical / & manual means including dressing sides, ramming of bottoms, providing barricading, danger lighting, shoring,strutting, dewatering, etc. IN ALL KINDS OF SOIL MIXED WITH BOULDERS of 30 cms size, etc. for: Pipes of all dia. for depth upto 2.0 M in all types of soils(BWSSB SR 17-18, P.51, I No.1.1)	Cum	167.00	Rupees One Hundred Sixty Seven Only
3	187.20	Supplying, lowering, laying, jointing, testing and commissioning of Glazed Stone Ware Pipes of following dia, conforming to IS 651:1992,IS 4127 with latest amendments, including conveying to work site, caulking with hemp dipped in tar and jointing with CM 1:1.5 using OPC, perfect linking and curing for 10 days and testing with water etc. with all lead, lifts and as per Technical Specifications. The cost to include the cost of all jointing materials, necessary survey works for laying of sewer lines etc. complete. The contractor will make own arrangements for procuring water for testing.230 mm dia. pipes(BWSSB SR 17-18, P.157 I.No 3.4)	m	523.00	Rupees Five Hundred Twenty Three Only
4	187.20	Labour charges for laying and jointing glazed stone ware pipes of 0.6m length and of specified dia., of tested quality conforming to IS 651 of 1965 including caulking with hemp yarn, jointing with CM 1:2 and testing with water etc. complete for: (Rate to include cost of jointing materials and transportation of pipes from store work site but excluding the cost of earth work) - Glazed Stone Ware pipe of 230 mm dia. (P.No.159 I. No.7.3 BWSSB 2017-18)	Rmt	108.00	Rupees One Hundred Eight Only
5	50.00	Providing house connection with excavation in all types of soils without damaging the other utilities and supplying and laying 25 mm OD MDPE pipe (PE80) manufactured in accordance with ISO 4427 - 1996 with minimum required strength of 8 Mpa, hydraulic design stress of 6.3 Mpa and with minimum wall thickness of 2.3 mm by making the bore of 15 mm dia. size on the Board's supply mains of 100 mm dia. using drilling bits or machines only and laying the pipe line at a depth not less than 0.45 mtrs. from the road surface, including providing 40 mm dia. "A" class GI pipe as casing over the MDPE pipe from the bore point and upto the entrance of the premises and removing the stone slab covering of the drain and dismantling the size stone masonry wherever necessary and making bore in the wall of the premises. On entering the premises, connection should be continued with 20 mm GI pipe by making "U" shape for the meter point below the ground level by making pit with sufficient space for the easy installation and removal of the water meter and providing vertical stand pipes on both sides of the mater. The connection should be secured firmly on the Board's main pipe with SS / Brass . ferrule of size 1/2" x 3/4"	Cum	3560.00	Rupees Three Thousand Five Hundred Sixty Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
6	122.92	Refilling pipeline and foundation with selected trenches available earth form trench excavation and foundation inlcuding 5 watering, consolidation in layers of 15cms., thickness including disposing off the surplus earth with all leads & lifts (BwsSB SR 2016-17 P-9 I-2)	Cum	62.00	Rupees Sixty Two Only
7	25.19	KSRRB M400-6.1 : Construction of granular sub-base by providing close graded cushed stone aggregates of granite / trap / basalt material, mixing in a mechanical mix plant at OMC, carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications. A. Plant Mix Method For Grading-II Material (BwsSB SR 2016-17, P-280 I-20.4)	Cum	1571.00	Rupees One Thousand Five Hundred Seventy One Only
8	33.59	Wet Mix Macadam, Providing.laying, spreading and compacting cushed stone aggregates of granite trap/basalt to wet mis macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of 4 mixed method of tipper to site, laying in uniform layers with paver in sub-base base course on well prepared surface and compacting with bratory roller to achieve the desired density complete as per specifications MORTH Specification No. 406 (RwssR SR 2016-17)	Cum	1668.00	Rupees One Thousand Six Hundred Sixty Eight Only
9	10.00	Dismantling the damaged or collapsed manhole of 4" dia conical in shape and reconstructing the same with machine made wire 6 brick in CM (1:4) as per design and specification of new cut manhole 4" dia with old frame and cover excluding bed concrete 13.6 (RwssR SR 2016-17, P-97, I-92 MTR DEPTH	Nos	7358.00	Rupees Seven Thousand Three Hundred Fifty Eight Only
10	1.00	Providing and constructing "wire cut brick manhole chambers" using sulphate resistant cement, conical in shape at top with C.C. 1:3:6 foundation using 40 mm and down size graded metal of approved quality and with an offset of 0.15 m alround the chamber and brick masonry in C.M. 1:4 plaster with wire cut bricks of approved quality and CM plaster 1:3 proportion 12 mm thick inside and outside except for the conical surface outside where the thickness of plaster shall be 20 mm thick, with 1:6 slope in the concrete towards the central drain, finished smooth and fixing of pipes in CC 1:2:4 graded metal of 20 mm and down size including conveying to work spot supplying & fixing SFRC manhole frame and cover confirming to IS:12592 with latest amendments in CC 1:2:4, supplying and fixing of minimum 3 mm thick encapsulated plastic footsteps (as per IS 10910) on 12 mm dia, Grade Fe-415 steel bar (as per IS 1786) staggered at 30 cms apart as detailed in Technical Specifications and as directed, watering, curring, barricading, danger lighting, pouring tar over MH frame and cover, cost of tar, shoring,	Nos	15704.00	Rupees Fifteen Thousand Seven Hundred Four Only
11	7.00	For 1.5 m depth	Nos	21479.00	Rupees Twenty One Thousand Four Hundred Seventy Nine Only
12	2.00	For 3 m depth	Nos	41745.00	Rupees Forty One Thousand Seven Hundred Forty Five Only
13	72.56	Disposong off the excess excavated earth of all type up to a distance mentioned Every Km beyond 5 KM 8 Considering 10 Km below by vehicle including loading unloading with all lifts labour HOM of machinery etc., complete (BWSSB SR 2016-17 Pg-10 Item-7)	Cum	147.00	Rupees One Hundred Forty Seven Only
14	15.00	Hire Charges for 2HP dewatering pump to bail out water at leaking pits inclusive of hire charges etc, complete Rs.1300/- per day of 8hours shift per day (BWSSB SR 16-17 Sl.No-4, P-34)	Days	1300.00	Rupees One Thousand Three Hundred Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
15	116.33	Cement concrete pavement.Construction of un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with OPC cement or any other type as per clause 1051.2.2 design mix M20/M30 , with 25mm and down size graded granite metal coarse aggregates and fine aggregtes , with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008 , mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane, selant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specifications. -	Cum	5210.96	Rupees Five Thousand Two Hundred Ten and Ninety Six Paise Only

01/02

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

01/02

Note:

1. Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
2. Unit rates and prices shall be quoted by the Tender in Indian rupees.
3. Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)
4. Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of Work:Suppy of Water through Water Tanker at Kodigehalli, Maruthinagar & B.B Nagar Area in Kodigehalli in Ward No 8.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	1002.00	Supply of Drinking Water through water tankers of Capacity 6000 Liters,Hring of Water Tanker (Page No. XLVIII, Code No. 1032) PWD SR 2018-2019 For 3000 Liter Capacity =412/2 = 206 2) Hiring of Tractor 40HP P XXXXVI / I No. 19, Code No 1023, PWD SR 2018-2019 Water 40.00 / KL (S.L No 745, Code No 0818). For 6KL= 6X40=240 Procurement of Water --Rs. 240.00/ Load (6000 Liters). Considering 3000 Liters cost is =240/2 Rs.120.00/Load Considering 5 Loads/Day 6X120.00=720 Engaging Causal Labours (Unskilled mazdoor Heavy) (PWD SR 2018-2019 Page No. LIV / I. 5) Subtotal for 6 loads,Consider 6 Loads / Day for 167 Days 6 X 165 = 1002 Loads x Rs. 443.37 =For 1 Load = 2660.20/6	Per Load	443.37	Rupees Four Hundred Forty Three and Thirty Six Paise Only

01/02

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

01/02

Note:

1. Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
2. Unit rates and prices shall be quoted by the Tender in Indian rupees.
3. Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)
4. Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of Work: Suppy of Water through Water Tanker at Balaji Layout and Bhadrappa Layout at Kodigehalli in Ward no 08

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	1002.00	Supply of Drinking Water through water tankers of Capacity 6000 Liters,Hring of Water Tanker (Page No. XLVIII, Code No. 1032) PWD SR 2018-2019 For 3000 Liter Capacity =412/2 = 206 2) Hiring of Tractor 40HP P XXXXVI / I No. 19, Code No 1023, PWD SR 2018-2019 Water 40.00 / KL (S.L No 745, Code No 0818). For 6KL= 6X40=240 Procurement of Water --Rs. 240.00/ Load (6000 Liters). Considering 3000 Liters cost is =240/2 Rs.120.00/Load Considering 5 Loads/Day 6X120.00=720 Engaging Causal Labours (Unskilled mazdoor Heavy) (PWD SR 2018-2019 Page No. LIV / I. 5) Subtotal for 6 loads,Consider 6 Loads / Day for 167 Days 6 X 165 = 1002 Loads x Rs. 443.37 =For 1 Load = 2660.20/6	Per Load	443.37	Rupees Four Hundred Forty Three and Thirty Six Paise Only

01/02

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

01/02

Note:

1. Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
2. Unit rates and prices shall be quoted by the Tender in Indian rupees.
3. Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)
4. Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ.

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of Work: Improvements to Parks in Kodigehalli Ward No 08

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	2.47	KSRRB M300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neately dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specification. MORTH / Chapter 3 (P.No.143, I.No.19.1 of PW, P&IWTD SR 2018-19)	Cum	252.49	Rupees Two Hundred Fifty Two and Forty Nine Paise Only
2	4.59	KSRB 4-1.2: Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.13, I.No. 4.2 of PW, P&IWTD S.R 2018-19)	Cum	5505.64	Rupees Five Thousand Five Hundred Five and Sixty Four Paise Only
3	4.54	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13(P.No.25, I.No.5.6 of PW, P&IWTD S.R 2018-19)	Cum	4871.76	Rupees Four Thousand Eight Hundred Seventy One and Seventy Six Paise Only
4	7.56	KSRB 15.1.1 Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. (P.No.115, I.No.15.1 of PW, P&IWTD S.R 2018-19)	Sqm	149.46	Rupees One Hundred Forty Nine and Forty Six Paise Only
5	3.04	KSRB 4-1.5 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregates @ 0.43 cum, machine mixed, concrete laid in layers not exceeding 15cms thick well compacted, in foundation and plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.(P.No.13, I.No. 4.5 of PWD SR 2018-19)	Cum	5647.68	Rupees Five Thousand Six Hundred Forty Seven and Sixty Eight Paise Only
6	2.29	KSRRB M300-53. Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300- 2 complete as per specifications, (which includes cost of gravel / murrum, watering charges & compaction by vibratory roller) MORTH Specification No. 305 (P.No.147, I.No.19.60 of PW,P&IWTD S.R 2018-19)	Cum	344.50	Rupees Three Hundred Forty Four and Fifty Paise Only
7	10.00	Providing and making precast seating arrangement including excavation laying pcc M15, providing laying M20 concrete for pedestal and seating slab, fixing of seating slab including all necessary bolt and nuts etc, complete and as per the directions of Engineer in-Charge. (Data Rate)	Each	11785.00	Rupees Eleven Thousand Seven Hundred Eighty Five Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
8	10.08	KSRB 5-11 : Providing and constructing load bearing wall with solid concrete blocks of size 400x200x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 5.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4 (P.No.27 I.No.5.27.1 of PW,P&IWTD SR of 2018-19)	Sqm	966.72	Rupees Nine Hundred Sixty Six and Seventy Two Paise Only
9	5.04	KSRB15-3.9 :Providing 18mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.(P.No.116 I.No.15.17 of PW,P&IWTD SR of 2018-19)	Sqm	259.70	Rupees Two Hundred Fifty Nine and Seventy Paise Only
10	1659.90	Fabricating, supplying & erecting M.S. angular Truss for all spans as approved design and drawing. The entire truss is anchored suitably by using 4 Nos. of M.S. anchor bolts at each support, with base plate and shoe plate.The work includes cutting, straightening, placing in position of M.S angle and wleding wherever necessary, and applying one coat of red oxide primer coat to all the members including cost of all materials, labour charges, & hire charges of machineries for cutting, welding, grinding & erection equipments, etc., complete as per specification. (Page No. 43 Item No. 7.20 of CSR 2018-19)	kgs	135.68	Rupees One Hundred Thirty Five and Sixty Eight Paise Only
11	34.00	Supplying and fixing new Mangalore tiles on existing reepers. (P.No.267, I.No.37.9 of PWD SR 2018-19)	Sqm	431.42	Rupees Four Hundred Thirty One and Forty Two Paise Only
12	45.10	KSRRB M800-7. Painting:-Providing and applying two coats of ready- mix paint of approved brand after through cleaning of surface to give an even shade complete as per specifications. MORTH Specification No. 803 Painting on Steel Surface(P No 181 I No24.8.1 of PW P&IWTD S R 2018-19))	Sqm	76.32	Rupees Seventy Six and Thirty Two Paise Only

01/02

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

01/02

Note:

1. Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
2. Unit rates and prices shall be quoted by the Tender in Indian rupees.
3. Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)
4. Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ.

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of Work: Improvements of Roads and Desilting at Devinagar and Surrounding area at Kodigehalli Ward No.8.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	208.37	KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete asper specifications MORTH / Chapter 3(I No-19 1 P No-143)	Cum	252.49	Rupees Two Hundred Fifty Two and Forty Nine Paise Only
2	22.22	KSRB 4-1.2 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms^thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification No. KBS 4.1, 4.2.(P.No-13,I No-4.2)	Cum	5505.64	Rupees Five Thousand Five Hundred Five and Sixty Four Paise Only
3	484.80	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specificaitons. Specification No. KBS 4.6.2(I No-4.31,P No-16)	Sqm	379.48	Rupees Three Hundred Seventy Nine and Forty Eight Paise Only
4	63.63	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mmand down size graded granite metal coarse aggregates @0.0.69cum and fine aggregtes @ 0.460cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintles, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No. KBS 4.1, 4.6(I No-4.11,P No-	Cum	5998.54	Rupees Five Thousand Nine Hundred Ninety Eight and Fifty Four Paise Only
5	3.18	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C workincluding straightening, cutting, bending, hooking, placing in position,lapping and / or welding wherever required, tying with binding wire andanchoring to the adjoining members wherever necessary complete asper design (laps, hooks and wastage shall not be measured and paid)cost of materials, labour, HOM of machinery complete as perspecifications.Specification No. KBS 4.6.3(I No-4.46.2 P No-18)	Tonne	75223.96	Rupees Seventy Five Thousand Two Hundred Twenty Three and Ninety Six Paise Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
6	190.80	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete. (Data Rate)	Sqm	1873.00	Rupees One Thousand Eight Hundred Seventy Three Only

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

"DTS APPROVED"

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of Work: Providing and Fixing CCTV on Black Spot in Kodigehalli Ward No.8

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	10.00	Supplying ,installation ,Commissioning and Testing CP PLUS 3 MP , 50 meters ip bullet camera,1/3" 3MP PS CMOS Image Sensor,Max 25fps@3MP, 25/30fps@1080P,H.264, H.264H, H.264B , MJPEG dual-codec encoding,DWDR, Day/Night(ICR), 3DNR, ROI, AWB, AGC, BLC, HLC,3.6mm fixed lens (6mm optional),IR Range of 50 Mtrs, IP67, SD Card, PoE,Mobile Software: iCMOB, gCMOB,CMS Software: KVMS Pro, vOptimus Pro inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	22160.00	Rupees Twenty Two Thousand One Hundred Sixty Only
2	1.00	Supplying ,installation ,Commissioning and Testing CP PLUS 32 Ch. H.265 4K Network Video Recorder Up to 32 channel IP camera input H.265/H.264 dual codec decoding Up to 8Mp resolution preview and playback Max 200Mbps incoming bandwidth Support 4 SATA HDDs up to 24TB, 2 USB(1 USB3.0) HDMI / VGA simultaneous video output Support Multi-brand network cameras ONVIF Version 2.4 conformance Mobile Software: iCMOB, gCMOB inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	65892.00	Rupees Sixty Five Thousand Eight Hundred Ninety Two Only
3	1.00	Supplying ,installation ,Commissioning and Testing Netgear ReadyNAS 4-Bay Diskless Network Attached Storage for Personal Cloud by Netgear inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	256420.00	Rupees Two Hundred Fifty Six Thousand Four Hundred Twenty Only
4	1.00	Providing and Supplying NAS hard disk drives 6 TB inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	23850.00	Rupees Twenty Three Thousand Eight Hundred Fifty Only
5	1.00	Supplying ,installation ,Commissioning and Testing D-Link 8-Port Gigabit Switch With 2 Combo SFP Ports inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	27500.00	Rupees Twenty Seven Thousand Five Hundred Only
6	1.00	Providing and Fixing Media converter Giga Dlink inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	11200.00	Rupees Eleven Thousand Two Hundred Only
7	2935.00	Providing and Fixing OFC cable single mode 6 core inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	m	165.00	Rupees One Hundred Sixty Five Only
8	1.00	Providing and Fixing Electrical work for boxes for power supply, fixing PVC Boards with three pin socktes and switches with protection MCB and cabling to street light electrical poles as per the direction of Engineer in Charge	Nos	7500.00	Rupees Seven Thousand Five Hundred Only
9	4.00	Providing Cctv MS poles with camera fixing brackets, 5 to 6 mtr height Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	23500.00	Rupees Twenty Three Thousand Five Hundred Only
10	4.00	Providing and Fixing MS Boxes for Poles with rust proof powder coating Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	8500.00	Rupees Eight Thousand Five Hundred Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
11	4.00	Providing and Fixing Electrical work for boxes for power supply, fixing PVC Boards with three pin socktes and switches with protection MCB and cabling to street light electrical poles as per the direction of Engineer in Charge	Nos	7500.00	Rupees Seven Thousand Five Hundred Only
12	1.00	Providing Internet charges connecting CCTV with IP Based for one month	Nos	3000.00	Rupees Three Thousand Only
13	1.00	Supplying ,installation ,Commissioning and Testing of 43" LED TV – Reputed make Sony/Samsung/LG inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	44000.00	Rupees Forty Four Thousand Only
14	1.00	Supplying ,installation ,Commissioning and Testing Server rack 15u Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	34500.00	Rupees Thirty Four Thousand Five Hundred Only

01/02

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

01/02

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

"NO CORRECTION N/C"
"DTS APPROVED"

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ.